

The acoustic Doppler effect applied to the study of linear motions

José A Gómez-Tejedor¹, Juan C Castro-Palacio²
and Juan A Monsoriu^{3,4}

¹ Centro de Biomateriales e Ingeniería Tisular, Universitat Politècnica de València, Camí de Vera s/n, 46022, València, Spain

² Departement Chemie, Physikalische Chemie, Universität Basel, Klingelbergstrasse 80, CH-4056 Basel, Switzerland

³ Centro de Tecnologías Físicas, Universitat Politècnica de València, Camí de Vera s/n, E-46022, València, Spain

E-mail: jogomez@fis.upv.es, juancarlos.castropalacio@unibas.ch and jmonsori@fis.upv.es

Received 3 November 2013, revised 26 November 2013

Accepted for publication 12 December 2013

Published 22 January 2014

Abstract

In this work, the change of frequency of a sound wave due to the Doppler effect has been measured using a smartphone. For this purpose, a speaker at rest and a smartphone placed on a cart on an air track were used. The change in frequency was measured by using an application for Android™, 'Frequency Analyzer', which was developed by us specifically for this work. This made it possible to analyze four types of mechanical motions: uniform linear motion, uniform accelerated linear motion, harmonic oscillations and damped harmonic oscillations. These experiments are suitable for undergraduate students. The main novelty of this work was the possibility of measuring the instantaneous frequency as a function of time with high precision. The results were compared with alternative measurements yielding good agreement.

Keywords: Doppler effect, smartphone, linear motion

(Some figures may appear in colour only in the online journal)

1. Introduction

The Doppler effect is a very important physical phenomenon with a great variety of applications nowadays. For example, some radars use this effect to determine the velocity of moving objects, and in astronomical sciences, the frequency change in electromagnetic waves is used to measure the speed of stars and galaxies. In medicine, the Doppler effect is used for the construction of images and for the measurement of blood flow. Other applications in satellite communication and acoustics have also been reported.

⁴ Author to whom any correspondence should be addressed.

The Doppler effect consists of a change in the frequency received by the receptor when the source moves relative to it, that is, the frequency increases when the receptor approaches the source and decreases when the receptor moves away from the source [1–7]. In our case, we have used a source at rest and a moving receptor. Then, the frequency registered by a moving observer, being the source at rest, is expressed by

$$f' = f \left(1 \pm \frac{v_0}{v} \right), \quad (1)$$

where f is the frequency of the source, v_0 is the velocity of the observer and v is the velocity of the wave, that is, the sound in the air. The plus sign indicates that the observer approaches to the source (the frequency increases), and the minus sign indicates that the observer moves away (the frequency decreases).

There are various articles on acoustic Doppler effect experiments reported in the literature [8–13], in which different layouts have been used. For instance, in [8] ultrasonic emitters placed at the end of a rotating arm were the moving sources and a fixed emitter provided a frequency for comparison. The signal was directed to a dual channel oscilloscope in order to detect a frequency shift or the sum of both signals on the oscilloscope display.

In [9] one speaker was carried by a student moving at a walking speed of about 1 m s^{-1} . The Doppler shifts was measured with a microphone and a digital frequency meter. They also measured Doppler shifts using the microphone and an oscilloscope to observe and measure the beat frequency produced between the moving speaker's shifted signal and the sound from a second stationary speaker. In [10] the authors used a Windows computer program and a sound card to record the Doppler-shifted sound from a moving speaker at constant velocity on an air track. They used a fast Fourier transform (FFT) analysis of the sound data to determine the peak positions visually, and subsequently the frequency shift. The precise determination of the peak centers was somewhat subjective. The authors also performed experiments on accelerated motions, measuring a frequency shift in the FFT representation for which a good qualitative agreement between the theory and the data was shown. In reference [11] a microphone was connected directly to the computer sound card and a small loudspeaker was attached to the end of a vibrating metal rod. The effect of the speaker speed on the frequency spectrum of the sound received by the microphone was observed. A Matlab[®] program was used to acquire the sound data and perform the FFT. The estimated value of the rod vibration frequency was consistent with the visual observation of the vibrating rod. In [12] the authors used a speaker attached to a string moving in uniform circular motion. The sound waves were recorded and Fourier analyzed. The calculated power spectrum of the measured sounds was represented over a few periods of time (sonograms). The theoretical curves of the measured sonogram were superposed yielding good agreement. In [13] the authors measured the instantaneous Doppler-shifted frequency of a free-falling sound source. The acceleration of gravity was calculated from the slope of the frequency versus time.

The main novelty of our work lies in being able to measure the frequency as a function of time with very high precision. For this purpose, a very simple measurement instrument is used, that is, a smartphone as a receptor which moves with respect to a speaker (source). No additional calculations are need. The smartphone shows the measured frequency as a function of time directly on the device display. This is an advantage with respect to previous experiments where a microphone, a speaker and a computer program to analyze the results were independent components. Here, the computer program and the receptor are integrated in a portable device.

In the present work, the experimental setup included a speaker connected to a signal generator and a smartphone attached to the cart of an air track. The single frequency signal emitted by the speaker is captured by the microphone of the smartphone. The speaker is

fixed while the smartphone may move on the air track with different relative velocities. The analysis of the signal was performed with the Android™ application ‘Frequency Analyzer’ [14]. Although a variety of applications are available in the Google Play™ repository which can be used for different physics experiments [15–20], we have not found any application capable of determining the fundamental frequency of the sound wave with sufficiently high precision for our purposes. For this reason, we have developed our own free application for Android [21].

The Doppler effect was used to characterize four mechanical motions, that is, the uniform linear motion, uniformly accelerated linear motion, simple harmonic oscillations, and damped harmonic oscillations, respectively. The main idea is that the frequency change measured from the Doppler effect is related to the speed of the smartphone which is placed on the cart of the air track. These experiments can be easily performed in a physical laboratory, in which an air track is available, and with a student’s smartphone. These experiments allow students to better understand the Doppler effect, and in addition, to study the different linear motions by an alternative method.

The outline of the paper is as follows. In section 2, the methodology for each experiment is described. In section 3, results for each of the four studied motions are discussed. Finally, in section 4, some conclusions are drawn.

2. Experiments

By using an air track, linear motions with speeds of less than 1 m s^{-1} can be studied. This means that the change in frequency due to the Doppler effect associated with these speeds should be less than 0.3%, so that, to obtain good results, the frequency has to be measured with very high precision. For this purpose, an Android™ application capable of measuring the fundamental frequency of sound with a precision of less than 0.04% and to sample the frequency every 0.1 s, was developed. We decided to implement our own application since no application for this purpose was available in the Google Play™ store online. However, we had to take into account that the sound produced by the air track when running can cause interference and consequently additional errors in the frequency measurement.

In order to quantify such errors, the frequency of a sound wave with 3000 Hz has been measured with the smartphone at rest on the air track with the air track switched on. The value measured by the smartphone was $(3000.1 \pm 0.5) \text{ Hz}$, which corresponds to a relative error in the measurement of the frequency of 0.017% and a discrepancy with the expected value of 0.003%.

From the arguments given above, we can conclude that this application can be used for measuring the Doppler effect since it is capable of measuring frequencies within a precision of 0.5 Hz for a signal of 3000 Hz, so that we are able to measure frequency changes for smartphone speeds starting from 0.06 m s^{-1} .

Figure 1 shows the experimental setup for the measurement of the frequency with the smartphone on the air track. The smartphone was moved with four different linear motions: uniform linear motion, uniformly accelerated linear motion, harmonic oscillations and damped harmonic oscillations. The figure shows the speaker (1) which emits the signal, the smartphone (2) attached to a cart on the air track (3), and the photometer which detects the cart passing through it (4) and activates the time counter (5) to measure the speed of the cart for uniform motion and the period of the oscillations for harmonic motion. For the harmonic motions, two springs were attached to the cart. In all experiments, the smartphone model Samsung Galaxy Mini S5570 was used. The signals of unique frequency were generated by connecting the speaker to an ac frequency generator.




Figure 1. Photograph of the experimental setup used to measure the frequency of a linear motion. In the figure, (1) is the speaker, (2) the air track, (3) the smartphone, (4) the photodetector and (5) the time counter.




Figure 2. Snapshots of the Frequency Analyzer application for two measurements of the frequency when the smartphone moves with uniform motion on the air track: (a) moving away from the speaker and (b) approaching the speaker.

In figure 2, two examples of the frequency measurement with the mobile phone are shown. In order to assure that the application correctly measured the frequency change due to the relative motion, the smartphone was left quiet for a few seconds, and afterwards was moved at approximately constant velocity. In both cases, the frequency of the source was 3000 Hz. In figures 2(a) and (b), the zone from which the experiment was begun can be clearly observed (labeled as (1) and (3), respectively), that is, the region where the frequency is constant. Once the motion was started (figure 2(a)), a decrease in the frequency was observed (2), since for this case, the receptor moved away from the source. Finally, when the smartphone got too far from the speaker (source), the amplitude of the signal received by the microphone decreased, and the application was not able to determine the frequency with precision. Those values should not be taken into account in the calculations. In figure 2(b), an increase in frequency is observed (4) since the mobile phone approached the source. In this case, the mobile phone was stopped when it reached the end of the air track, and the initial constant frequency can be observed again (5).




Figure 3. Snapshot of the application window for a measurement of the frequency in a simple harmonic motion.

In the first experiment, for the uniform linear motion, the cart was moved with approximately constant velocity. By means of a photometer, the pass of the cart (with the smartphone) moving at constant velocity was detected, and by means of a time counter the elapsed time was measured. The speed of the cart was then calculated by dividing the distance traveled over the time elapsed. This value was later compared with the result derived from the Doppler effect.

In the second experiment, for the uniformly accelerated linear motion, the air track was set at the inclination of (0.030 ± 0.001) rad which allowed a component of the gravity acceleration to act along the air track direction,

$$a = g \sin \alpha = (0.294 \pm 0.013) \text{ms}^{-2}. \quad (2)$$

For the third and fourth experiments, the cart was attached to two fixed points by means of two equal springs. In figure 3, an example of the measurement of the frequency by the smartphone moving with simple harmonic oscillations is shown. The frequency of the source was 3000 Hz. In the figure, the sinusoidal variation of the signal is clearly observed. From the data obtained in this measurement, the amplitude is calculated as 7.5 Hz, which corresponds to the maximum speed in the harmonic motion, 0.85 m s^{-1} .

Finally, the case of the damped simple harmonic oscillations was presented. The air supply of the air track was decreased to allow some friction between the air track and the cart with the smartphone attached.

3. Results and discussions

3.1. Uniform linear motion

In figure 4, the frequency as a function of time in a uniform linear motion is shown. During the first 1.6 s, the smartphone was at rest (red circles) and registered a frequency of (3000.1 ± 0.3) Hz. From this moment on, the cart was moving at constant velocity (green boxes), for a




Figure 4. Frequency versus time in a uniform linear motion. Red circles represent the mobile phone at rest, and the green boxes show when it moved away from the source.

frequency of (2995.0 ± 0.7) Hz registered by the mobile phone. Once the smartphone moved far away from the speaker, the intensity of the sound signal decreased and the application was not able to determine the frequency with precision (after 2.6 s). The measurements for times longer than 2.6 s were not included in the calculations.

With these data, and taking into account that the speed of sound at the temperature of the experiments, $24\text{ }^{\circ}\text{C}$, is 347 m s^{-1} [22], the speed of the cart (with the smartphone) was calculated. The resulting value was $(0.592 \pm 0.002)\text{ m s}^{-1}$, which was compared with the value obtained from using the photo-detector and the chronometer, $(0.585 \pm 0.009)\text{ m s}^{-1}$. A strong agreement between both results for a percentage discrepancy of 1.2% was obtained.

3.2. Uniformly accelerated linear motion

Figure 5 shows the results for the speed as obtained from the frequency shift due to the Doppler effect for the mobile phone moving with uniformly accelerated linear motion. A small corrugation in the signal with a duration of 0.08 m s^{-1} approximately can be observed. This is related to small variations of the frequency measured around 0.7 Hz in this case. During the first 3 s, the smartphone remained at rest and from this moment on, it started moving under the action of the component of the gravity force that appeared due to the inclination of the air track. For a uniformly accelerated linear motion the acceleration is constant and equals the slope of the curve of the velocity versus time. The % calculation yielded $(0.303 \pm 0.021)\text{ m s}^{-2}$. This represents a discrepancy of 3% with the value obtained from equation (2).

3.3. Free simple harmonic motion

The values of the velocity versus time as calculated from the frequencies measured with the smartphone moving with simple harmonic oscillations are shown in figure 6. The experimental data was fitted to the equation of the velocity of the simple harmonic motion,

$$v(t) = v_0 \cos(\omega_0 t + \phi_0). \quad (3)$$

The values of the parameters resulting from the fitting were $v_0 = (0.57 \pm 0.02)\text{ m s}^{-1}$ (amplitude), $\omega_0 = (4.414 \pm 0.007)\text{ rad s}^{-1}$ (natural frequency of the system) and




Figure 5. Absolute value of the velocity versus time for a uniformly accelerated linear motion. Blue crosses represent the experimental data, and the red line the linear fit.




Figure 6. Velocity of the smartphone versus time for the data obtained from the simple harmonic motion. Blue crosses represent the experimental data, and the red curve the fit.

$\phi_0 = (4.91 \pm 0.07)$ rad (initial phase). From the value of the frequency ω_0 , the period of the oscillatory motion can be calculated, $T = (1.423 \pm 0.002)$ s. This value was compared with the measurement of the time counter, $T_{tc} = (1.428 \pm 0.001)$ s. A very low discrepancy of 0.3% between both measurements was obtained.

3.4. Damped simple harmonic motion

In figure 7, the results of the speed as calculated from the frequency measured with the smartphone moving with damped simple harmonic oscillations are shown. The graph clearly shows the underdamped behavior of the system. A decrease in the amplitude with time can be observed, which is due to the friction force between the cart and the air track. The time




Figure 7. Velocity of the smartphone calculated from the data obtained in the damped simple harmonic motion. Blue crosses represent the experimental data, and the red curve represents the fit.

dependence of the position as a function of time in an underdamped harmonic motion is given by the following expression:

$$x(t) = Ae^{-\gamma t} \sin(\omega t + \phi_0), \quad (4)$$

where A is the amplitude of the motion, γ is the damping constant, ω is the damped angular frequency and ϕ_0 is the initial phase. The damped frequency is a function of the natural frequency calculated in the previous experiment and of the damping constant, that is, $\omega^2 = \omega_0^2 - \gamma^2$. By taking the first derivative with respect to time, the expression for the velocity is obtained,

$$v(t) = Ae^{-\gamma t} (-\gamma \sin(\omega t + \phi_0) + \omega \cos(\omega t + \phi_0)). \quad (5)$$

The fitting of the experimental results to this equation yielded the following values for the parameters: $A = (0.206 \pm 0.006)$ m, $\gamma = (0.050 \pm 0.003)$ s⁻¹, and $\phi_0 = (1.17 \pm 0.02)$ rad.

From the value of the damping constant, and the natural angular frequency calculated in the previous experiment, the damped frequency was obtained, $\omega = (4.414 \pm 0.007)$ rad s⁻¹. The system was weakly damped, that is $\gamma \ll 1$, and the damped frequency was nearly equal to the natural frequency, so that the differences between them were less than the error obtained in the fit.

4. Conclusions

The Doppler effect was studied by using a speaker and a smartphone as useful laboratory measurement instruments. The single frequency sound signal emitted by a speaker was captured by the microphone of the smartphone. The speaker was fixed while the smartphone moved on an air track with different types of mechanical motions. The frequency change as a function of time was measured with high precision using our own Android™ application ‘Frequency Analyzer’ developed specifically for this work. Four experiments were performed. In the first case, the constant velocity of the cart was measured by the Doppler effect, and by using a time counter was compared with a discrepancy of 1.2%. In the second experiment, a uniformly accelerated motion was studied. The acceleration calculated from the speed derived

from the Doppler effect was compared to the value calculated from Newton's second law, taking into account the inclination angle of the air track. A discrepancy of 3% between the results indicated very good agreement. Free and damped harmonic motions were also studied. A good agreement between the experimental data and the theoretical expressions was also obtained.

Acknowledgments

The authors would like to thank the Institute of Education Sciences, Universitat Politècnica de València (Spain) for the support of the Teaching Innovation Groups, e-MACAFI and MoMa.

References

- [1] Doppler C A 1842 Über das farbige Licht der Doppelsterne und einiger anderer Gestirne des Himmels (http://de.wikisource.org/wiki/Über_das_farbige_Licht_der_Doppelsterne_und_einiger_anderer_Gestirne_des_Himmels)
- [2] Tipler P A and Mosca G 2008 *Physics for Scientists and Engineers* (San Francisco: Freeman) chapter 15
- [3] Neipp C, Hernández A, Rodes J J, Márquez A, Beléndez T and Beléndez A 2003 An analysis of the classical Doppler effect *Eur. J. Phys.* **34** 497–505
- [4] Donges A 1998 A simple derivation of the acoustic Doppler shift formulas *Eur. J. Phys.* **19** 467
- [5] Rothenstein B and Sabata A D 1998 Frequency shifts for accelerated sources and observers: an illustration of non-locality in frequency measurement *Eur. J. Phys.* **18** 569–74
- [6] Saknidy S 1985 Doppler's effect and four dimensional space *Eur. J. Phys.* **6** 104–7
- [7] Kapoulitsas G M 1981 On the non-relativistic Doppler effect *Eur. J. Phys.* **2** 174–7
- [8] Bianchetti G B and Ganci S 1994 A quantitative acoustical Doppler-shift experiment *Eur. J. Phys.* **15** 157–61
- [9] Cox A J and Peavy Joel J 1998 Quantitative measurements of the acoustic Doppler effect using a walking speed source *Am. J. Phys.* **66** 1123–5
- [10] Bensky T J and Frey S E 2001 Computer sound card assisted measurements of the acoustic Doppler effect for accelerated and unaccelerated sound sources *Am. J. Phys.* **69** 1231–6
- [11] Azooz A 2007 Experimental demonstration of Doppler spectral broadening using the PC sound card *Am. J. Phys.* **75** 184–8
- [12] Spicklemire S J and Coffaro M A 2006 The treatment of reflections in a Doppler measurement using the method of images *Am. J. Phys.* **74** 40–42
- [13] Torres S M and González-Espada W J 2006 Calculating g from acoustic Doppler data *Phys. Teach.* **44** 536–9
- [14] Gómez-Tejedor J A 2013 Frequency analyzer <http://play.google.com/store/apps/details?id=fqan.frequencyanalyzer>
- [15] Vogt P and Kuhn J 2012 Analyzing simple pendulum phenomena with smart-phone acceleration sensor *Phys. Teach.* **50** 439–40
- [16] Kuhn J and Vogt P 2012 Analyzing spring pendulum phenomena with a smart-phone acceleration sensor *Phys. Teach.* **50** 504–5
- [17] Castro-Palacio J C, Velazquez-Abad L, Gimenez M H and Monsoriu J A 2013 Using a mobile phone acceleration sensor in physics experiments on free and damped harmonic oscillations *Am. J. Phys.* **81** 472–5
- [18] Castro-Palacio J C, Velazquez-Abad L, Gimenez F and Monsoriu J A 2013 A quantitative analysis of coupled oscillations using mobile accelerometer sensors *Eur. J. Phys.* **34** 737–44
- [19] Sanz J A, Manjon F J, Pereira A L J, Gomez-Tejedor J A and Monsoriu J A 2013 Oscillations studied with the smartphone ambient light sensor *Eur. J. Phys.* **34** 1349–54
- [20] Kuhn J and Vogt P 2013 Analyzing acoustic phenomena with a smartphone microphone *Phys. Teach.* **51** 118–9
- [21] <http://developer.android.com>
- [22] Lide D R 2005 Speed of sound in dry air *CRC Handbook of Chemistry and Physics* (Boca Raton, FL: CRC Press) www.hbcpnetbase.com